SMITH COLLEGE
NORTHAMPTON, MASSACHUSETTS
OFFICE OF THE SUPERINTENDENT

May 19, 1953

Miss Janet R. White
Martha Wilson House
Smith College
Northampton, Mass.

Dear Miss White:

Our estimate for coupling the radio transmitter of the College Radio Station to one of our high voltage feeders in transformer vault T-11 is NINE HUNDRED TWENTY-FIVE DOLLARS ($925.00).

As discussed with Mr. Albert King we are to furnish and install 2-5000 volt oil cutouts in the vault; connect two (2) capacitors (which are to be furnished by Mr. Albert King) in the vault and install a 2" conduit from the vault to the outside of the Radio Station; this conduit to terminate in an outdoor cabinet to be furnished by Mr. Albert King. The equipment in this cabinet will also be furnished by Mr. King.

I am sure you understand this estimate is for our part of the work only. I have no idea what Mr. Albert King's estimate of costs may be.

Very truly yours,

Geo. W. King

George W. King
Superintendent

GWK/mck